

## ADDENDUM NO. 1

City of Snoqualmie, Washington  
Snoqualmie Parkway Rehabilitation Project  
CONTRACT # HLP-MAWA (002)

DATE OF ADDENDUM ISSUE: April 21<sup>st</sup> 2023  
DATE OF BID OPENING: May 2<sup>nd</sup> 2023

### NOTE TO ALL PLANHOLDERS:

This Addendum No. 1, containing the following revisions, additions, deletions, and/or clarifications, is hereby made a part of the Plans and Contract Specifications (Contract Documents) for the above-named project. Bidders shall take this Addendum into consideration when preparing and submitting their bids.

Bidders shall acknowledge receipt and acceptance of this Addendum No. 1 in the space provided on the Bid Summary or by signing in the space provided below and submitting the signed addendum with the bid package. Failure to provide this written acknowledgment may result in disqualification of the Bidder's submittal.

### CONTRACT SPECIFICATIONS

#### 1. Special Provisions

##### Section 1-07.18 Insurance APWA GSP (SP 25-SP 28)

DELETE this GSP in its entirety. Refer to the insurance requirements set forth in **Section 000 04 30 Insurance Requirements** of the Contract Provisions (pages 31-34).

#### 2. Special Provisions

##### Section 7-05.1 Construction Requirements (SP 87)

REPLACE the last sentence of the first paragraph with the following:

This work shall also consist of cleaning catch basin out by vactor truck prior to physical completion **when requested by the Engineer.**

DELETE the second paragraph of this section.

#### 3. Special Provisions

##### Section 7-05.3 Construction Requirements (SP 88)

REPLACE the second bullet point of the 1<sup>st</sup> paragraph with the following:

- Installing HMA cold patch around utility if left in place at existing grade between grinding and paving operations. Contractor must pave final overlay within **7 calendar days** of grinding operations with this protection option.

**4. Special Provisions**

**Section 7-05. 3 Construction Requirements (SP 88)**

ADD the following paragraph:

The Contractor shall be responsible for keeping catch basins within and adjacent to the construction activities free from construction debris during construction. The Engineer shall inspect catch basins prior to physical completion and request that any catch basins with significant amounts of sediment or construction debris be cleaned using a vactor truck. This work, when required, shall be considered incidental to the various bid items of the contract and no additional payment shall be made.

**5. Special Provisions**

**Section 8-01.5 Payment (SP 94)**

ADD the following paragraph:

All costs associated with preparing and maintaining the SWPPP shall be considered incidental to the lump sum bid price for *“Erosion Control and Water Pollution Prevention”*.

**6. Special Provisions**

**Section 8-20.3(14)C Induction Loop Vehicle Detectors (SP 117)**

ADD the following paragraph:

Loops shall be placed before the final paving lift. Cutting the loops in after the final paving is complete will not be allowed.

---

**ALL OTHER REQUIREMENTS OF THE CONTRACT DOCUMENTS REMAIN IN EFFECT.**

**Addendum No. 1 is hereby made a part of the Contract Documents, and its terms and conditions are fully binding on the Contract Documents holder. He/she shall acknowledge receipt of Addendum No. 1 by filling out 1.07 Acknowledgment of Addenda on page 00 03 00 – 6 in the Form of Bid or by signing in the space provided below and submitting the signed addendum with the bid package.** Failure to provide this written acknowledge may result in disqualification of the Bidder’s submittal.

Receipt acknowledge, and conditions agreed to this \_\_\_\_\_ day of \_\_\_\_\_, 2023

Bidder \_\_\_\_\_  
Signature

**Pre-Bid Walk Thru Sign-in Sheet**  
**City of Snoqualmie Parkway Rehabilitation**  
**10:00 AM April 19, 2023**

Name	Title	Company	Phone	E-mail
Jeff Hamlin	Deputy Public Works Director	City of Snoqualmie		jhamlin@snoqualmiewa.gov
Hind Ahmed	Project Engineer	City of Snoqualmie		hahmed@snoqualmiewa.gov
Wayne Green	PROJECT MANAGER	WATSON Asphalt	425-868-4377	rschroeder@watsonasphalt.co
Dave Enger	TRAFFIC ENGINEERING CONSULTANT	KPG PSOMAS		dave.enger@psomas.com
David Pavolka	Estimating	Tucci and Sons	(253)298-5958	drp@tucciandsons.com
Tyler Townsend	Project Manager	ICON Materials	253-293-4391	tyler.townsend@iconmaterials.com
Mark Eichelberger	Construction Manager	ICON	253 561-1451	Mark.Eichelberger@iconmaterials.com
Bill Johnson	Estimator	Icon Materials	253-261-4852	Bill.Johnson@Iconmaterials.com